



May 11, 2025

Project: Wastewater Treatment Plant Lift Station Control Panel Replacement

Customer: **City Of Lago Vista**

T. Morales Company is pleased to offer the following as our proposed scope of work for the electrical installation for this project and as identified above.

**Clarifications**

- Label and disconnect all the power and control wiring in the lift station control panel.  
Panel includes nema 4x stainless steel enclosure.  
Audible and visual alarm beacon.  
24vdc power supply.  
4 seal fail/ overtemp relays.  
Control transformer.  
Digital panel meter.  
Push buttons and lights  
Terminal blocks.
- Provide and install a new lift station control panel.
- Install new level transmitter.
- Install 2 new float switches.
- Connect all wiring and test.
- Lead time is 8-10weeks

**Total Price.....\$28,500.00**

**Items Excluded:**

- Anything outside the clarification
- Permit Fees

I can be reached at the office (254-793-4344) mobile (512-844-5374) or email ([jwoolverton@moralescompany.com](mailto:jwoolverton@moralescompany.com)) if you may have any further questions regarding this proposal.

Sincerely;  
T. Morales Company  
Jason Woolverton  
Estimating

*Jason Woolverton*